

DATE: October 30, 2019

CLARIFICATION NO. 1
TO
CONSTRUCTION DOCUMENTS
FOR PROJECT NO. E008283

DESCRIPTION: **AML SITE 1813, Cougar Highwall**

LOCATION: **SULLIVAN COUNTY, INDIANA**

FOR AGENCY: **DEPARTMENT OF NATURAL RESOURCES**

The information contained in this Clarification is intended to correct any composition errors and serve to eliminate any misunderstanding of the basic plans and specifications the same as if being originally incorporated therein.

ITEM NO. 1: The Contractor shall provide for in-situ density tests in the quantity listed on the Schedule of Supplemental Unit Prices. Density tests will be at the discretion of the Division's Project Manager and may or may not be utilized for this project. If density test are determined to be necessary by the Project Manager, they shall be performed where directed for the purpose of insuring uniform compaction of at least 95%. Compaction will be necessary in areas of water impoundment and areas in the immediate vicinity of the known subsidence. Compaction methods are described in Section 203.03 of the 2010 AML Standard Specs.

ITEM NO. 2: All trees shall be felled by March 31, 2020.

END OF CLARIFICATION