

**ADDENDUM NO. 1
TO
SPECIFICATIONS
FOR
PROJECT NO. E030311**

DESCRIPTION OF PROJECT: NEW LAKE DAM PRIMARY & EMERGENCY SPILLWAY REPAIRS

LOCATION: FORT HARRISON STATE PARK – MARION COUNTY, IN

ISSUE DATE: December 21, 2017

INDIANA STATE AGENCY: DEPARTMENT OF NATURAL RESOURCES

The information contained in this Addendum shall become a part of the basic plans and specifications, the same as if originally incorporated therein. The original plans and specifications shall remain in their entirety, except as modified by this Addendum. The items herein shall supersede information in the Specifications and on the plans.

ITEM No. 1:

SECTION 01720 – PROJECT RECORD DOCUMENTS

1.02 MAINTENANCE OF DOCUMENTS:

- B. Remove “These drawings must be submitted before the final payment.” Replace with “These drawings shall be submitted in electronic PDF format and approved before the final payment.”**

ITEM No. 2:

SECTION 02271 – AGGREGATE PLACEMENT AND LAKE DEWATERING

1.01 SCOPE

- C. ADD: Discharge pipes from dewatering operations shall be placed in the existing Emergency Spillway or Primary Spillway Plunge Pool. It shall be the Contractors responsibility to ensure that under no circumstance shall any sediment be allowed**

from the discharge pipes. The Contractor shall be responsible for removal of all sediment discharge from the drawdown pipes.

ITEM No. 3:

SECTION 02530 – PIPE RELINING

1.11 DIMENSIONS

- A. Diameters: ADD: 54” OD pipe liner for the 60” diameter pipe and 36 “ OD for the 42” pipe as per INDOT Specification 725 – Slip Lining Of Existing Pipe**