

**Date: March 23, 2018**

**ADDENDUM NO. 1  
TO  
PLANS AND SPECIFICATIONS  
FOR  
PROJECT NO. ENG1801724495**

**DESCRIPTION OF PROJECT:** Boat and Vehicle Parking Paving Project-2018

**LOCATION:** Paynetown State Recreational Area

**ISSUE DATE:** March 23, 2018

*MSM*

**INDIANA STATE AGENCY:** DEPARTMENT OF NATURAL RESOURCES

**The information contained in this Addendum shall become a part of the basic Specifications, the same as if originally incorporated therein. The original Specifications shall remain in their entirety, except as modified by this Addendum. The items herein shall supersede information in the Specifications.**

The following items reflect clarifications to the Plans-Specifications for the bid of this project.

**ITE ITEM NO. 1:** Plans and Specifications

**Clarification: All Sheets: The owner has a location approximately 0.50 miles away that can be used for disposal of waste or stump removal. If the contractor needs suitable earthen fill material for shoulder grading, then the owner has material at the same location that can be used by the contractor.**

**ITEM NO. 2:** Plans and Specifications

**Clarification: Sheet 3: The contractor shall allocate 12 new wheel stops in their bid for the replacement of existing and new installations. Care shall be exercised upon removal of existing to save as many as possible. If excess wheel stops remain upon completion they shall be delivered to the owners' location for storage.**

**ITEM NO. 3:** Plans and Specifications

**Clarification: Sheet 4 Attached: Pavement striping changes and clarification. Accessible space and aisle removed.**

**ITEM NO.4:** Plans and Specifications

**Clarification: Sheet 5: The contractor shall allocate 30 new wheel stops in their bid for the replacement of existing and new installations. Care shall be exercised upon removal of existing to save as many as possible. If excess wheel stops remain upon completion they shall be delivered to the owners' location for storage.**

**ITEM NO. 5:** Plans and Specifications

**Clarification: Sheet 6 Attached: Pavement striping changes and clarification. Accessible space and aisle dimension changes.**

**ITEM NO. 6:** Plans and Specifications

**Clarification: Sheet 7: The contractor shall allocate 35 new wheel stops in their bid for the replacement of existing and new installations. Care shall be exercised upon removal of existing to save as many as possible. If excess wheel stops remain upon completion they shall be delivered to the owners' location for storage.**

**ITEM NO. 7: Plans and Specifications**

**Clarification: Sheet 7: See Typical Section D. The subbase for this work at this location is existing aggregate. The owner is adding fill and rip rap at the NE and SE corners of Area "E" to repair erosion damage. Their work will be finished and in place before construction. Remove the stump that was flush cut and root ball west of the vicinity of the "D" symbol. Backfill and restore as per typical section "B".**

**ITEM NO. 8: Plans and Specifications**

**Clarification: Sheet 8 Attached: Pavement striping changes and clarification. Accessible space and aisle added, cross walk added, dimension changes, angled parking changed to parallel.**

**The sign in sheet from the March 21, 2018 Pre-Bid Meeting is attached.**

**END OF ADDENDUM**

TITLE	_____
JOB	_____
BY	_____
DATE	_____

March 21, 2018 10:00 am  
DNR - Paynetown PAVING  
Pre Bid

Sign in

<u>Name</u>	<u>Company</u>	<u>Email</u>
Brad Bender	FPBH, Inc.	bbender@fpbhonline.com
Garrett Gough	E+B Paving	garrett.gough@ebpaving.com
AJ Chandler	Milestore	aj.chandler@milestorepa.com
Jeff Wettrick	All Star Paving	jeffw@allstarpaving.net
Cory Krimm	DNR-Monroe Lake	ckrimm@dnr.in.gov
BEN SMITH	IDNR-ENGINEER	bsmith@dnr.in.gov
Michael Mathias	IDNR Engr.	mmathias@dnr.in.gov
James Roach	IDNR - MONROE	JROACH@DNR.IN.GOV