

## ADDENDUM

---

**Client:** Department of Natural Resources  
**Project:** Pokagon State Park Toboggan Run Piping Upgrades  
**Client Project No.:** ENG2003780646  
**Applied Project No.:** 19-110  
**Addendum No.:** 3  
**Date:** 11/27/2020

The following changes and clarifications shall be incorporated into the Contract Documents for the above-referenced project. The information contained herein modifies the original Bidding Documents and all prior Addenda as applicable. Requirements of the original Bidding Documents and previous Addenda remain in effect except as modified by this Addendum. Bidders must acknowledge receipt of this Addendum on the Bid Form. Failure to acknowledge receipt of this Addendum may subject Bidder to disqualification.

### **Bidding Questions**

1. QUESTION: Is an outer jacket of 150mm rather than 50mm desired?
  - a. RESPONSE: A jacket thickness of 50mm is acceptable. See changes to the hydronic piping specification this Addendum #3.

### **SPECIFICATIONS**

#### 232113 HYDRONIC PIPING

1. Delete paragraph 3.1.A.1 in its entirety.
2. Add paragraph 3.1.A.1 with the following text:  
*Cased piping, schedule 40 PVC carrier pipe with 1"thick polyurethane carrier pipe insulation and 50 mil thick HDPE casing.*

**END**